


SAFE DRINKING WATER AND SANITARY CONDITION CERTIFICATE

It is certified that an inspection team headed by **Sanjay Dubey Quality Manager & Chemist District Water Testing Laboratory PHED Vidisha** Distt. Vidisha inspected the **Vatsalya Sr. Sec. School, Haripura, Vidisha** on **03.04.2024** and found that the **Vatsalya Sr. Sec. School, Vidishahas safe drinking water facilities** for the student and member of staff of the institution and they **maintaining the hygienic sanitation condition** in the school building & the campus as per norms prescribed by the Central/State/ U.T. Govt..

To,

Vatsalya Sr. Sec. School

Haripura, Vidisha




Signature with Seal

Name : Sanjay Dubey

Designation : Quality Manager & Chemist

Name & Address of the Deptt. :

District Water Testing Laboratory PHED Vidisha


Manager
Vatsalya Sr Sec School
Vidisha (M.P.)
Principal
Vatsalya Sr. Sec. School
Vidisha (M.P.)
रसायनज्ञ
जिला जल परीक्षण प्रयोग शाला
लोक सभा स्थल, बामिकी, विदिशा

DISTRICT WATER TESTING LABORATORY PHED Division VIDISHA
Near Ramlila Maidan Drainage colony Mandi road Vidisha -464001

Test Report



Date 04.04.2024

Desp. No.311

Report No 311 Date 04.04.2024

A Name and address

Principle, Vatsalya School Vidisha

2. Particulars of a sample place of collection & Details

B Reference No. Nil/03.04.24
3 Date and Time of sample receive 03.04.24
4 Date of analysis start 03.04.24
3 Date of analysis end 03.04.24
4 Unique ID 43.- 44
5 Condition of the sample Ok/Not Ok OK

43	Vidisha - Raw Water
44	Vidisha - Tap Water

S.No.	Name of parameter	Name of test methods used	BIS 10500:2012 Reaffirmed in Sep. 2018		Unit	Unique ID				
			desireble limits	Permissible limits		43	44			
1	Tempraturte	Celsius			Degree C	22C	22C			
2	Turbidity	part 10	1	5	NTU	1.10	0.50			
3	Colour	part 04	5	15	Hazon Scale	Nil	Nil			
	Taste	Part 7, 8	Agreeable	Not Agreeabl	None	Agreeable	Agreeabl			
4	Odour	part 05	Agreeable	Not Agreeabl	None	Agreeable	Agreeabl			
5	pH	Part 11	6.5 -8.5	No relax.	pH Scale	7.52	7.43			
6	Conductivity	Part 16			Micromho/cm	1080	220			
7	Total solids	Part 16	500	2000	Mg/L	637	130			
8	Total Alkalinity	Part 23	200	600	Mg/L	121	34			
9	Total Hardness as Caco3	Part 21	200	600	Mg/L	490	128			
10	Ca as Ca++	Part 40	75	200	Mg/L	122	49			
11	Mg as Mg++	Part 46	30	100	Mg/L	34	23			
12	Chloride	Part 32	250	1000	Mg/L	140	48			
13	Nitrate as No3	Part 34	45	45	Mg/L	15.00	2.00			
14	Iron	Part 53	0.3	0.3	Mg/L	0.13	0.08			
15	Fluoride	Part 60	1	1.5	Mg/L	0.32	0.10			
16	Sulfate	Part 24	200	400	Mg/L	10.00	3.10			
17	Magnese	Part 59	0.1	0.3	Mg/L	Nil	Nil			
18	Arsenic	Part 37	0.01	0.05	Mg/L	Nil	Nil			
19	Feacal coliform	Part 10	0/100	0/100	per 100 ml	0.00	0.00			
20	Total coliform	Part 10	0/100	0/100	Per 100 ml	0.00	0.00			

- Note: 1 Sample has been provided by the customer and Sample tested as received.
2 The result applied to sample as received.
3 Report shall not be reproduce except in full without approval of the laboratory.
4. Sample will be retained for 15 days.

Signature of analyst
District water testing laboratory Vidisha (M.P.)

[Signature]
Manager
Vatsalya Sr. Sec. School
Vidisha (M.P.)

[Signature]
Principal
Vatsalya Sr. Sec. School
Vidisha (M.P.)

[Signature]
Sanjay Dubey
Authorised Signatory & Quality manager
District Water testing laboratory Vidisha (M.P.)